

പതിനാലാം കേരള നിയമസഭ

ഒന്നാം സമ്മേളനം

നക്ഷത്രചിഹ്നമിടാത്ത നിയമസഭാ  
ചോദ്യം നമ്പർ - 576

30.06.2016 ലെ മറുപടിയ്ക്ക്

**കുറ്റ്യാടി ഇറിഗേഷൻ പ്രോജക്ടിന്റെ കനാലുകൾ  
ബലപ്പെടുത്തുന്നതിനും മെയിന്റനൻസിനുമായി സമഗ്രമായ  
ഒരു പാക്കേജ് നടപ്പിലാക്കാൻ നടപടി**

ചോദ്യം

മറുപടി

ശ്രീ.കെ.ദാസൻ

ശ്രീ.മാത്യു.ടി.തോമസ്  
(ജലവിഭവ വകുപ്പ് മന്ത്രി)

(എ) കുറ്റ്യാടി ഇറിഗേഷൻ പ്രോജക്ട് നിലവിൽ വന്നത് എന്നാണ്; വ്യക്തമാക്കാമോ?

(എ) കുറ്റ്യാടി ഇറിഗേഷൻ പ്രോജക്ട് 1963 ൽ ആരംഭിക്കുകയും 1993 ൽ പൂർത്തീകരിക്കുകയും ചെയ്തു.

(ബി) ഈ പ്രോജക്ടിന്റെ ഭാഗമായുള്ള മെയിൻ കനാൽ, ബ്രാഞ്ച് കനാൽ, ഡിസ്ട്രിബ്യൂട്ടറി എന്നിവ ഏതെല്ലാമാണ്; കൊയിലാണ്ടി മണ്ഡലത്തിലൂടെ കടന്ന് പോവുന്നത് ഏതെല്ലാമാണെന്ന് വിശദമാക്കാമോ;

(ബി) മെയിൻ കനാൽ, ബ്രാഞ്ച് കനാൽ, ഡിസ്ട്രിബ്യൂട്ടറി എന്നിവയുടെ പേരും വിശദവിവരങ്ങളും അനുബന്ധമായി ചേർത്തിരിക്കുന്നു.

(സി) കുറ്റ്യാടി ഇറിഗേഷൻ പ്രോജക്ട് കനാലിന്റെ പല ഭാഗങ്ങളും നാശാവസ്ഥയിലാണ് എന്നും ഇത് കാരണം വേനൽ കാലത്ത് വെള്ളമെത്താത്ത അവസ്ഥ കൊയിലാണ്ടിയിലെ മിക്ക പഞ്ചായത്തുകളിലും ഉണ്ടായി എന്നതും പ്രസ്തുത പ്രശ്നവുമായി ബന്ധപ്പെട്ട് കൊയിലാണ്ടി തഹസിൽദാരുടെ ഓഫീസ് ജനപ്രതിനിധികൾ ഖെരാവോ ചെയ്തു എന്നതും ശ്രദ്ധയിൽപ്പെട്ടിട്ടുണ്ടോ;

(സി) ശ്രദ്ധയിൽപ്പെട്ടിട്ടുണ്ട്.

(ഡി) കുറ്റ്യാടി ഇറിഗേഷൻ പ്രോജക്ടിന്റെ വിവിധ കനാലുകൾ ബലപ്പെടുത്തുന്നതിനും മെയിന്റനൻസിനുമായി സമഗ്രമായ ഒരു പാക്കേജ് നടപ്പിലാക്കാൻ നടപടി സ്വീകരിക്കുമോ;

കുറ്റ്യാടി ഇറിഗേഷൻ പ്രോജക്ടിന്റെ വിവിധ കനാലുകൾ ബലപ്പെടുത്തുന്നതിനും മെയിന്റനൻസിനുമായി പ്രധാൻ മന്ത്രി കൃഷി സിൻചായി യോജനയിലെ (Pradhan Mantri Krishi Sinchayee Yojana-PMKSY) ആക്സിലറേറ്റഡ് ഇറിഗേഷൻ ബെനിഫിറ്റ് പ്രോഗ്രാമിലെ (Accelerated Irrigation Benefit Programme-AIBP) ജില്ലാ ജലസേചന പദ്ധതിയിൽ (District Irrigation Plan-DIP) ഉൾപ്പെടുത്തുന്നതിന് വേണ്ടി 209.50 കോടി രൂപയുടെ നിർദ്ദേശങ്ങൾ തയ്യാറായി വരുന്നു.

(ഇ) പതിനായിരക്കണക്കിന് കുടുംബങ്ങളുടെ കടിവെള്ള ആവശ്യം എന്ന നിലയിൽ ഇതിന് പ്രാഥമിക പരിഗണന നൽകുമോ?

*(Handwritten mark)*

*(Handwritten signature)*

സെക്ഷൻ ഓഫീസർ

Bramanmu o

Sl. No.	Name Of Canal	Position below Head works off take point	Length in Kms
I. Left Bank Main Canal 40.22 Km.			
1.	Pillaperuvanna FB	1.150 L	1.250
2.	Vengappetta FB	11.100 R	0.270
3.	Karuvannur Distributary	15.200 L	5.100
4.	Nochad Distributary	20.200 L	4.620
5.	Edavarad Distributary	22.700 L	4.260
6.	FB At 32100 M	32.100	0.100
7.	FB At	35.280	0.220
8.	Direct Sluices		
II. Kallur Branch Canal 12.045			
1.	Perambra FB	3.015 L	1.044
2.	FB At 10800 M	10.800 R	0.400
3.	FB At 12045 M	12.045 (T.E)	0.545
4.	Direct Sluices		
III. Kakkodi Br. Canal 35.330 Km			
1.	FB At 210 M	0.210 L	2.550
2.	Peruvancheri FB	3.300 R	1.650
3.	Kottoor FB	3.350 R	1.700
4.	FB At 3800 M	3.800 L	0.840
5.	Poonath Distributary	4.320 L	5.400
6.	Naduvannur Distributary	6.850 R	0.340
7.	Narath Distributary	13.100 R	3.420
8.	Modakkallur FB	14.950 R	0.840
9.	Cheekkilode Distributary	19.900 R	4.830
10.	FB At 18825 M	18.825 L	0.900
11.	FB At 19975 M	19.975 R	0.225
12.	FB At 19.975 M	19.975 L	0.165
13.	FB At 20250 M	20.250 R	0.160
14.	Pavandoor FB	21.200 L	3.090
15.	Edakkara Distributary	22.000 R	2.150
16.	Pattarpalam FB	22.400 R	1.700
17.	Kannankara FB	23.375 R	3.050
18.	Ichannur Sub Distributary	24.950 R	3.400

19.	Maruthad FB	25.000 L	1.600
20.	Thamarassery FB No. I	26.150 R	3.510
21.	Thamarassery FB No. Iii	27.035 R	1.850
22.	Palath FB	28.460 R	1.500
23.	Moorikkara Distributary	29.000 R	5.300
24.	Moottoli FB	31.710 R	3.100
25.	Direct Sluices & Tail End Distributaries (Puthiyangadi And Chevayur)	35.330	10.230
IV. Naduvathoor Br. Canal 13.620 Km.			
1.	Avala Distributary	0.750 R	4.875
2.	Vilayathur Distributary	6.300 R	1.550
3.	Cheruvannur Muyipoth Distributary	1.200 R	5.460
4.	Thurayur Distributary	6.700 L	3.000
5.	Keezhariyur FB	11.000 R	1.250
6.	Direct Sluices		
V. Ayanicad Br. Canal 10.100 Km			
1.	Thiruvangayur F B	2.225 R	1.425
2.	Ekkallur FB	3.200 R	0.815
3.	Nochad FB	4.420 R	0.975
4.	Kavil FB I	5.500 R	1.000
5.	Kavil FB II	6.030 L	0.390
6.	Direct Sluices		
VI. Thiruvangoor Br. Canal 7.500 Km			
1.	Kanayankode Distributary	2.400 L	2.400
2.	Thiruvangoor Distributary	7.500	3.500
3.	Direct Sluices		
VII. Iringal Branch Canal 19.320 Km			
1.	Kodakkad Distributary	R	1.550
2.	Vellarakkad Distributary	L	2.625

3.	Chingapuram Distributary	R	1.130
4.	Thikkodi Distributary	L	2.325
5.	Kilur Distributary	R	1.830
6.	Kannankulam Distributary	L	2.000
7.	Panthalayini FB	L	1.850
8.	Kalankandi FB	R	0.260
9.	Viyyur FB	R	0.600
10.	Purakkad FB	L	2.000
11.	Pallikkara FB	R	0.638
12.	Ayanikkad FB	L	1.910
13.	Iringal FB		1.400
14.	Direct Sluices		

**Particulars of off take from Right Bank Main Canal (RBC)**

Sl. No	Name of Canal	Position below Head works off take point	Length in Kms
I Right bank main canal 34.200 Km.			
1.	Changaroath FB	1.030 L	2.740
2.	Palleri distributary	3.030 L	4.745
3.	Kayakkodi distributary	19.220 L	2.780
4.	Thaliyil distributary	19.635 L	3.800
5.	Perumundasseri distributary	25.850 L	2.900
6.	Edacherry distributary	30.900 R	7.500
7.	Thiruvallur distributary	30.230 L	9.625
8.	Direct sluices		
II. Velom Br. canal 4.200 Km			
1.	Velom distributary	4.200 (TE)	4.880
2.	Ayanchery distributary	4.200 R	3.200
3.	Direct sluices		

III. Tuneri Br. canal 7.650 Km			
1.	Vilathapuram FB	0.750 L	1.000
2.	Vilathapuram FB No II	1.380 L	1.350
3.	FB at 1408 M	1.408 R	
4.	Purameri distributary	2.575 L	2.910
5.	Nadapuram FB	3.775 R	1.500
6.	Velloor FB	4.220 L	0.700
7.	Perode FB	6.300 R	2.440
8.	Kodenchery distributary	7.630 L	2.500
9.	Tail end distributary	7.650	4.750
10	Direct sluices		
IV. Azhiyur branch canal 15.90 Km			
1.	Orkkattery distributary	8.400 R	3.400
2.	Eramala distributary	11.680 R	5.020
3.	Karthikappally distributary	0.990 R	2.085
4.	Kurinjalliyode distributary	1.552 R	1.230
5.	Chorode distributary	2.960 R	5.170
6.	Vaikkilissery distributary	4.095 R	2.000
7.	Uralungal FB	9.500 L	0.700
8.	Thattolikara distributary	12.620 L	2.00
9.	Kallamala distributary	16.580 L	0.60
10	Direct sluices		
V Maniyur Branch Canal 10.690 Km			
1.	Maniyur FB	R	2.000
2.	Poovanpuzha sub distributary	R	4.000
3.	Villiappally distributary	2.400 L	3.390
4.	Nadakkuthazha distributary	3.500 R	4.590
5.	Chemmarathoor distributary	4.280 R	4.800
6.	Puduppanam distributary	4.600 R	2.400
7.	Thodannur distributary	6.150 L	2.880
8.	Modappilavil distributary	7.650 R	1.650
9.	Maniyur (DS) distributary	10.690 T E	
10	Cherandathur distributary	10.690 L	
11	Direct sluices		

കൊയിലാണ്ടി മണ്ഡലത്തിലൂടെ കടന്നുപോകുന്ന കനാലുകളുടെ വിവരം  
താഴെ പറയുന്നു

1) ഇടുക്കര മെയിൻ കനാൽ 38/500 കി. മീറ്റർ മുതൽ 40/220 കി.മീറ്റർ നടേരി ഡിസ്ട്രിബ്യൂട്ടറി (1/500 കി. മീറ്റർ മുതൽ 4/850 കി. മീറ്റർ വരെ കുതിരക്കൂട ഫീൽഡ് ബോത്തി കാവുവട്ടം ഫീൽഡ് ബോത്തി കാവാര വട്ടം ഫീൽഡ് ബോത്തി

തിരുവങ്ങൂർ ബ്രാഞ്ച് കനാൽ- 7/500 കി. മീറ്റർ

തിരുവങ്ങൂർ ഡിസ്ട്രിബ്യൂട്ടറി- 3/500 കി. മീറ്റർ

കണയൻകൊട് ഡിസ്ട്രിബ്യൂട്ടറി- 2/400 കി. മീറ്റർ

കാളകണ്ടി ഫീൽഡ് ബോത്തി- 260 മീറ്റർ

പന്തലായിനി ഫീൽഡ് ബോത്തി- 850 മീറ്റർ

പുളിയൻചേരി ഫീൽഡ് ബോത്തി- 1/070 കി. മീറ്റർ

കാക്കുളം ഫീൽഡ് ബോത്തി- 450 മീറ്റർ

കൊടക്കാട് ഡിസ്ട്രിബ്യൂട്ടറി- 1/550 കി. മീറ്റർ

വെള്ളക്കാട് ഡിസ്ട്രിബ്യൂട്ടറി- 2/625 കി. മീറ്റർ

വിയൂർ ഫീൽഡ് ബോത്തി- 600 മീറ്റർ

പുറക്കാട് ഫീൽഡ് ബോത്തി- 1/100 കി. മീറ്റർ

ചിങ്ങപുരം ഡിസ്ട്രിബ്യൂട്ടറി- 1/130 കി. മീറ്റർ

തിക്കോടി ഡിസ്ട്രിബ്യൂട്ടറി- 2/325 കി. മീറ്റർ

പള്ളിക്കര ഫീൽഡ് ബോത്തി- 638.60 മീറ്റർ

കിലൂർ ഫീൽഡ് ബോത്തി- 1/840 കി. മീറ്റർ

അയിനിക്കാട് ഫീൽഡ് ബോത്തി- 2/325 കി. മീറ്റർ.

കണിയാംകുളം ഡിസ്ട്രിബ്യൂട്ടറി- 1/600 കി. മീറ്റർ

ഇരിങ്ങൽ ബ്രാഞ്ച് കനാൽ- 15/032 കി. മീറ്റർ

*M. M. M.*

സെക്ഷൻ ഓഫീസർ

