

# പതിനാലാം കേരള നിയമസഭ

**ഏഴാം സമ്മേളനം**

**നക്ഷത്ര ചിഹ്നമിടാത്ത ചോദ്യം നം.396**

**08-08-2017 ൽ മറുപടിക്ക്**

**കിഫ്ബി മുഖേന നടപ്പിലാക്കുന്നതിന് ഭരണാനുമതി നൽകിയ പദ്ധതികൾ**

ചോദ്യം <b>ശ്രീ. കെ. എം. മാണി</b>	മറുപടി <b>ശ്രീ. ടി.എം. തോമസ് ഐസക്</b> (ധനകാര്യവും കയറും വകുപ്പു മന്ത്രി)
(എ) 2016-17, 2017-18 എന്നീ സാമ്പത്തിക വർഷങ്ങളിൽ കിഫ്ബി മുഖേന നടപ്പിലാക്കുന്നതിന് ഭരണാനുമതി നൽകിയ പദ്ധതികളിൽ ടെണ്ടർ പൂർത്തിയാക്കിയവയുടെ പട്ടിക ലഭ്യമാക്കുമോ ;	2016-17, 2017-18 എന്നീ സാമ്പത്തിക വർഷങ്ങളിൽ കിഫ്ബി മുഖേന നടപ്പിലാക്കുന്നതിന് ഭരണാനുമതി നൽകിയ പദ്ധതികളിൽ ടെണ്ടർ പൂർത്തിയാക്കിയവയും അവയുടെ നിർവഹണ പ്രക്രിയയിലെ നിലവിലെ സ്ഥിതിയും അനുബന്ധം 1 ആയി ചേർക്കുന്നു.
(ബി) ഇവയിൽ എത്ര പദ്ധതികളുടെ നിർവഹണം ആരംഭിച്ചുവെന്ന് വ്യക്തമാക്കുമോ;	
(സി) ഇവയിൽ എത്ര പദ്ധതികളുടെ നിർവഹണം പൂർത്തീകരിച്ചിട്ടുണ്ട് ; ഇല്ലെങ്കിൽ കാലതാമസത്തിനുള്ള കാരണമെന്തെന്ന് വ്യക്തമാക്കുമോ ?	കിഫ്ബി ധനസഹായത്തിനായി സമർപ്പിക്കപ്പെട്ട പദ്ധതികൾക്ക് ഭരണസമിതിയായ ബോർഡിന്റെ അംഗീകാരം നവംബർ 2016 മുതൽ ജൂലായ് 2017 വരെയുള്ള കാലയളവിലാണ് ലഭിച്ചിട്ടുള്ളത്. അംഗീകാരം ലഭിച്ച പദ്ധതികളുടെ ടെണ്ടർ നടപടികൾ പൂർത്തിയായതിന് ശേഷം ശരാശരി മൂന്ന് വർഷം ആണ് ഒട്ടുമിക്ക പദ്ധതികളുടെയും നിർവഹണ കാലയളവ്. സമയബന്ധിതമായി തന്നെ എല്ലാ പദ്ധതികളും പൂരോഗമിച്ചു വരുകയാണ്. കാലതാമസം ഉണ്ടായിട്ടില്ല.



**സെക്ഷൻ ഓഫീസർ**

## Status of Projects

Sl. No.	Department Name	Main Project Name	Sub Project Name	Project Outlay (Rs. In Crore)	Tender Status	Work Status
1	Health & Family Welfare	Cath Labs, Basic Infrastructure in MCC, KCC, MHH Thiruvananthapuram, Kozhikode (100)	Setting up of Cathlab & CCU	80.00	Tendered	Work Started
2	Health & Family Welfare	Cath Labs, Basic Infrastructure in MCC, KCC, MHH Thiruvananthapuram, Kozhikode (100)	Setting up of Dialysis Centres	69.00	Tendered	Work Started
3	PWD	137 Roads	Improvements to Ambalapuzha Thiruvalla road	69.50	Tendered	Work Started
4	PWD	137 Roads	Improvements to Kalavoor Kattoor Beach road	20.80	Tendered	
5	PWD	137 Roads	Improvements to Cherthala-Thannermukkom Road CH 0/000-5/950	12.80	Tendered	
6	PWD	137 Roads	KIIFB Project: Improvements to Kaithavana Pazhayanadakkavu Ambalappuzha Vadakkenada road	20.20	Tendered	

Status of Projects - KWA							
1	Water Resources	WRD002-02	WSS in 10 Municipalities	<p>Augment ation of Urban Water Supply to Shornur Municipa lity and Vaniyam kulam Panchaya th</p> <p>Package I-a) Construction of 20mld WTP including 9LL Sump and pump house -Rs.13.25 cr b) Supplying and Laying 450mm DI K9 Clear Water Pumping main for a length of 2675m from WTP c) Supplying and Laying 300mm DI K9 Clear Water Pumping main from WTP to zone -I OHSR for 150m -Rs.0.10 cr d)Supply and erection of Raw water &amp; Clear Water pumpsets &amp; electrical works</p> <p>Package II - Provision for completing weir across river Bharathapuzha</p>	35	Kerala Water Authority	<p>Placed in KWA Board held on 07/06/2017 Lowest bidder is Sri. Joseph John, Muvattupuzha 18.06% below</p> <p>WORK TENDERED</p>
2	Water Resources	WRD002-03	WSS in 10 Municipalities	<p>Augment ation of 24mld WTP at Kallisserry &amp; Renovati on of 33mld WTP at Thiruvall a for Thiruvall a &amp; Changan aserry Municipa lities &amp; adjoining Panchaya ths</p> <p>Package I :- 1)Construction of 10 mld WTP at Kallisserry, Construction of 35 mld capacity aerator at Kallisserry including all channels - App A 2) Renovation of 25 mld Kallisserry Plant - App B 3) Construction of compound wall at Kallisserry - App C 4) Renovation of 33 mld Thiruvalla plant - App D 5) New Raw/Clear water pump sets at RW Pump house, CW pump house at Kallisserry Thirumoolapuram PH, Thiruvalla PH - App E</p>		Kerala Water Authority	<p>Re tendered Tender under processing in H.O Lowest bidder is J&amp;B Engineering &amp; Construction company 7.11% above</p>

Placed in KWA Board held on  
07/06/2017  
Lowest bidder is Sri. Joseph John,  
Muvattupuzha  
18.06% below

WORK TENDERED

Re tendered  
Tender under processing in H.O  
Lowest bidder is J&B Engineering  
& Construction company  
7.11% above

Sl. No.	Project Name	Project Code	Project Category	Project Description	Project Cost (Rs. Lakhs)	Project Status	Project Remarks
	Water Resources	WRD002-03	WSS in 10 Municipalities	<p>Augment ation of 24mld WTP at Kalliserry &amp; Renovati on of 33mld WTP at Thiruvalla for Thiruvalla &amp; Changan aserry Municipa lities &amp; adjoining Panchaya ths</p> <p>Package II:- 1) Construction of 15 LL OHSR at Thirumoolapuram &amp; Construction of 2LL sump at Thirumoolapuram - App A  2) Construction of 22LL OHSR at Thiruvalla &amp; construction of Office complex Thiruvalla -App-B  3) Laying transmission to Thirumoolapuram sump &amp; pumping to OHSR-App-C  4) Clear water PM from Thiruvalla sump to OHSR - App D  5) Distribution frm Thirumoolapuram OH Tank -App E  6) Distribution to Kuttupuzha area in Thiruvalla Municipality- App F  7) Construction of new roads and improvements of existing roads -App G  8) Installation of solar panel for power production - App H</p> <p>Package III:- 1) Construction of 15 LL OHSR at Thiruvandoor- App A  2) Construction of 15 LL capacity OHSR at Kuttoor-App B  3) Laying pumping mains to Thiruvandoor- App C  4) Laying clear water pumping main to Kuttoor OH Tank - App D  5) Distribution for Kottoor panchayath -App E  6) Distribution forThiruvandoor panchayath -App F</p> <p>Dedicated feeders to Kalliserry intake and WTP,Thiruvalla office compound</p>	58	Kerala Water Authority	<p>Work Order Issued on 13/6/17  Lowest bidder is Sri. Abu Mathew  JV with Sri. Shaji P.C  3.67% below</p> <p>1) Location: 26.26 cents private land for 15 LL OHSR at Kuttoor in Kuttoor village. Survey no. 175/10, 175/11, 175/7, 175/13 G.O issued from Revenue dept.</p> <p>2) Land for 15 LL OHSR at Thiruvandoor obtained from Panchayat</p> <p>Location : Parayankuzhy near Kalliserry  20 cents required  Status : Panchayath resolution for handing over obtained , waiting for sanction from Panchayath Director.</p> <p>To be deposited to KSEB</p>

3	Water Resources	WRD002-04	WSS in 10 Municipalities	Augment ation of Water Supply Scheme to Kollam Corporati on Phase -II	<p>Package I - Supplying, laying, Commissioning and maintaining 1219mm M.S RW Pumping Main from Intake to TP at vasoorichira</p> <p>Package II :-Construction of 20LL OHSR at TP site</p> <p>Package III :-Supplying, laying, Commissioning and maintaining 1016mm dia.8.8mm thick M.S Clear Water pumping main from TP to OHBR at Manichithod, 914mm MS CWGM from Manichithod to Anandavalleswaram and Construction of 54LL OHSR at Manichithod,</p> <p>Package IV:- Supply,erection,commissioning and maintaining of Raw Water pump sets and Electrical Sub stations at Intake</p>	235	<p>Deviation proposal to be submitted. In order to avoid delay in acquisition of land, alternate proposal for avoiding the balancing reservoir at Pottimukku and to lay pumping main from intake to Vasoorchira TP is considered and 1219mm OD MS pipe of 12.5mm barrel thickness is required for the entire stretch of PM from the intake up to the inlet level of aerator. Estimate is under scrutiny</p> <p>TP &amp; 20LL OHSR at Vasoorchira - 3.50 Acres ( Land to be acquired from private parties by Corporation) included in AMRUT. BVR has been submitted to the District Collector by the LA Tahsildar, Kundara.Meanwhile the corporation authorities have been contacted and requested to give an undertaking to the effect that the land for TP will be made available within short period and we can proceed with tendering procedure for TP &amp; other components sanctioned in KIIFB without waiting for handing over of the land.</p> <p>Estimate will be prepared while progressing the works of other packages</p>

S.No	Department	Project Name	Area	Sub Area	Project Description	Project Status	Remarks
					Package V:- Supply,erection,commissioning and maintaining of Clear Water pump sets and Electrical Sub stations at TP site		Estimate will be prepared while progressing the works of other packages
4		WRD002-05		WSS to Kasargode Municipality and Chemmanad Panchayath - Phase - I	Package 1- a) Raw water pumpset 350HP VT Pumpset(3Nos) b) Transformer 1250KVA including sub station and sub station building c)Raw water pumping main- 700mm DI - 1200m length d)Clear water pumping main-600mm DI - 700m length e)Balancing reservoir 11LL at Bovikkanam		Placed in KWA Board held on 07/06/2017 Lowest bidder is Sri. K.Kannan, Kannur 11.02% below
					Package II-a) 55MLD WTP including clear water sump, compound wall etc. b) Clear water pump house,3 Nos 60HP clear water pumpset and 1000KVA transformer, sub station and substation building		Placed in KWA Board held on 07/06/2017 Lowest bidder is Sri. K.Kannan, Kannur 17.59% below
					Package III-3 Nos. reservoir for Kasaragode Municipality -21 LL at Vidyanagar,5LL at Vidyanagar 12LL at Pulikkunnu and Gravity main for Kasaragode Municipality	76	Tender under scrutiny in H.O Lowest bidder is Sri. K.Kannan, Kannur 9.96% above

5	Water Resources	WRD002-06	WSS in 10 Municipalities	Package IV-Gravity main for Chemmanad and Construction of 2 Nos. reservoir for Chemmanad Panchayath -26LL at Deli Kunnupara and 17LL at Kunnupara Chattanchal	74.4	Kerala Water Authority	1) Private Land to be acquired for the construction of 26 LL OHSR at Deli Kunnupara(Re-Survey No.132-2A2R(30 cents), 132-2A2B2(20 cents)- Perumbala village - Total 50 cents 2)Private Land to be acquired for construction of 17 LL OHSR at Kunnupapara Chattanchal to be obtained(Survey No.248/1B(32 Cents)& 248-1C(8 cents)-Thekkil village - Total- 40 cents Request sent to GOK vide Lr No. 1587/DM I/(SU)/2017 dated 31-01-2017 LA proposal submitted to the District Collector, Kasaragod on 7/1/2017
				Package I- Well cum pump house,1016mmOD 12mm Thick M.S RWPM,WTP,CWSump,CW PumpHouse,Data Acquisition and Monitoring,Construction of Retaining wall & Compound wall,Construction and Commissioning of staff quarters etc			Placed in KWA Board held on 07/06/2017 Lowest bidder is Sri. Shahul Hameed, 2.46% below (Quoted amt Rs. 38.84 cr)
				Package II- 1. 700 mm DI K9 Clear Water Pumping Main			Placed in KWA Board held on 07/06/2017 Lowest bidder is M/s Reena Engineering company(pvt) ltd 13.92% below
				Package-III-Construction of Transformer Substation Building and shift Room,Raw Water Pump sets,Clear Water Pumpsets,Transformer and allied Electrical Works etc			Estimate under preparation and will be tendered later

6	Water Resources	WRD002-07	WSS in 10 Municipalities	WSS to Koyilandy Municipality	<p>Package-I</p> <ol style="list-style-type: none"> <li>1. Laying Transmission Main from Kayanna to Urallur Junction (900 DI – 5530m, 800 DI- 2545m, 600 DI – 6840m &amp; 500 DI – 100m)</li> <li>2. Laying Transmission main to Kottur (Zone I) Exst. GL Tank (200 DI- 1640m)</li> <li>3. Renovation of Exst. GL Tank for Kottur Zone – 1</li> </ol>	85	Kerala Water Authority	<p>Willingness of lowest bidder called for since the sanction is conditional . The tenderer has not submitted the same. Work order issued</p> <p>Lowest bidder is Reena Engineers &amp; Contractors Pvt. Ltd 14.55% below</p>
					<p>Package-II</p> <ol style="list-style-type: none"> <li>1. Laying Transmission Main from Urallur Junction to Koyilandy Municipality (500 DI – 1330m, 450 DI- 4640m, 350 DI – 7385m, 400mm HDPE- 600m.</li> <li>2. Construction of 3 Nos. Service Reservoirs to Koyilandy Municipality.</li> <li>3. Laying Transmission mains to Kottur Zone -2 and Naduvannur (350 DI – 330 m &amp; 250 DI -200m)</li> <li>4. Construction of Booster station and Erection of Pumpsets for Koyilandy Zone -1</li> </ol>			<p>Placed in KWA Board held on 07/06/2017</p> <p>Lowest bidder is Sri. Shahul Hameed, Malappuram 1.58% below (Quoted amt Rs. 21.92cr) TPAC -Rs. 22.27 cr</p>
					<p>Package-III</p> <ol style="list-style-type: none"> <li>1. Laying Transmission Main from Urallur Junction to Thurayur Panchayath (500 DI – 3810m, 300 DI- 6525m)</li> <li>2. Construction of Service Reservoir for Thurayur Panchayath.</li> <li>3. Construction of Service Reservoirs for Kottur Zone-2 and Naduvannur Panchayaths.</li> </ol>			<p>Status-3 private Land to be acquired for reservoirs for Kottur zone-2, Naduvannur &amp; Thurayur</p> <p>(1) Valloramala (Naduvannur) 25 Cent / 14 LL GL Tank</p> <p>(2) Valloramala (Kottur Zone-2) 25 Cent/13 LL GL Tank</p> <p>(3) Pakkanarpuram (Thurayur) - 7.5LL</p> <p>G.O issued from WRD for Kottur &amp; Naduvannur pchyts</p>



Estimate					Project Details		
7	Water Resources	WRD002-08	WSS in 10 Municipalities	<p>Package-I</p> <p>1. Modification &amp; Cleaning of existing 12m. Dia well cum pump house &amp; Providing additional Switch room (Near Mooppilkadavu Bridge).-30.00 lakh</p> <p>2. Formation of WTP site including Construction of Retaining wall-99.39 lakh</p> <p>3. Construction of 15.00 MLD Treatment plant (Additional).-1025.00 lakh</p> <p>4. Supply and erection of raw water pump sets (175 HP VT-3Nos.)-92.08 lakh</p> <p>5. Supply and erection of Clear water pump sets.- 66.54 lakh</p> <p>6. Supply and Erection of 630 KVA transformer at Intake point- 79.00 lakh</p> <p>7. Supply and Erection of 630 KVA transformer at WTP- 81.00 lakh.</p>	34	Kerala Water Authority	Work Order Issued Lowest bidder is Sri. A.Dominic, Thodupuzha 14.62 % below
				<p>Package-II</p> <p>1. Laying raw water pumping main.(600 mm DI K9 1800 m.)- 236.84 lakh</p> <p>2. Laying Clear water pumping Mains (450mm to 100mm DI K-9= 18150m)-662.58 lakh</p> <p>3. Laying Clear water Gravity Mains (400mm to 100mm DI K-9= 3665m)- 205.21 lakh</p> <p>4. Construction of Ground level Service reservoirs.</p> <p>1) 0.90 LL at Uravappara for Zone 5</p> <p>2) 11.50 LL at Pattanikkunnu (Additional) for Zone I- 146.32 lakh</p> <p>5. Construction of Over Head Service Reservoir. (15.0 LL at Bengalamkunnu for Zone 2) – 297.12 lakh</p> <p>6. Construction of Over Head Service Reservoir. (6.0 LL at Konakkamala for Zone 4)- 150.26 lakh</p> <p>7. Construction of damage roads to WTP and KWA office.- 50.00 lakh.</p>			Retendered since Quoted amt is 11.93% above  Tender opening (10/07/2018)
				<p>1. Power line extension of 11 KV Air Bunched cable and Power Allocation-86.68 lakh</p>			To be deposited to KSEB

Sl. No.		Project Name		Project Details		Project Cost (Lacs)		Remarks	
8	Water Resources	WRD002-09	WSS in 10 Municipalities	Augmentation of UWSS to Kottayam Municipality	Package-I 1. Pipe laying work which include laying of pumping lines ,gravity lines and main distribution lines ,interconnection work to existing tank in KWA campus. 2. Laying pipelines at various locations to strengthen / improve the distribution system in the Municipality. 3.Installation of 2 sets of CF Pump sets	50		Kerala Water Authority	Abstract of estimate revised allocating total amount of 26.58cr towards 50mld WTP and adjusting the cost of individual components so that the total cost is limited to the original amt.
					Package-2 1. Construction of 50mld treatment plant at Peroor				Package 2 will not be done if the tender for the work of 50mld plant at Peroor under NRDWP-WSS to Vijayapuram which is under the consideration of Hon' High Court is admitted
9	Water Resources	WRD002-10	WSS in 10 Municipalities	WSS to Thrissur Corporation and adjoining panchayaths Phase -1	Package-I 1. Construction of 12 m dia well cum pump house at Thirukuzhi 2. Construction of compound wall at Intake well cum Pump House 3. Raw water pumping main 1200 DI K9-300 mm 4.Construction of Counterfort Retaining wall for side protection of Pipe line road- 5.Construction of water treatment plant 100 MLD and providing SCADA arrangements - 6.Design, Supply & Installation of Surge arrester in 1200mm Raw water pumping main.	185		Kerala Water Authority	1) Purambokku land is available for intake well. 2) 5.13 acres of private land purchase is required for WTP in sy no: 365/2, 366/2,366/4, 366/1,68(old),367/5,367/6,367/7 in Vallachira and Arattupuzha villages.  G.O issued from WRD  Working estimate under scrutiny
					Package II 1. Design & Construction of R.C.C. foot bridge at Kanimangalam 2. Laying Clear water Pumping main 1100mm DI K9/MS pipe from Thirukuzhy WTP to Kanimangalam -9860m 3. Design, Supply & Installation of Surge arrester in 1100mm Clear water pumping main.				
				WSS to Thrissur Corporation	Package III 1. Laying Clear water Pumping main 900 mm DI K9 pipe from Palakkal to Kuriachira Junction - 4150 m 2. Laying Clear water Pumping main 800mm DI K9 pipe from Kuriachira Junction to Mylipadam Road - 3850m				Corporation land identified for OHSR at Kuriyachira for 50 cents & Nedupuzha for 17 cents. Request submitted to corporation to hand over the land to KWA.

	Water Resources	WRD002-10	10 Municipalities	on and adjoining panchayaths Phase -1	Package- IV 1. Raw water pump sets-410 HP VT -2 Nos-140 lakh 2. Clear water pump sets-350 HP Centrifugal pump sets-5 Nos-500 lakh 3. Supply and installation of transformers and other related electrical installations at intake well and WTP compound.- 400 lakh		Kerala Water Authority  Estimate will be prepared during the progress of work of WTP
10	Water Resources	WRD002-11	WSS in 10 Municipalities	WSS to Mattanur and Iritty Municipalities	Package I - Intake well-cum-Pump house Raw Water Pumping Main (750mm MS and 750 DI K9) Raw water pumpset (600 VT Pumpsets - 2 Nos) Transformer including substation building	76.6	Placed in KWA Board held on 07/06/2017 Lowest bidder is Reena Engineers & Contractors Pvt. Ltd 10.0% below
					Package II- Treatment Plant (42 MLD) Clear Water Reservoir (34 LL) at TP site Pump house Clear Water Reservoir 22 lakhs litre capacity near WTP Clear Water Pumpset ( 25 HP CF )		Placed in KWA Board held on 07/06/2017 Lowest bidder is M/s. Laxmi Civil Engineering Services Pvt. Ltd. 14.56% below
					Package III- GL Tank (3LL at Manja and 15 lakhs litre at PRNSS College) Clear Water Gravity Main 250mm DI K9 to Kotheri tank, 3100m Clear Water Pumping Main (200mm DI K9 to OH tank at Manjakunnu 2400m Clear Water Gravity main 400mm DI, 300mm DI to GL tank at PRNSS College 6600m Laying 450mm DI and 300m DI for connecting distribution lines 1000m		1) For Manja 3LL GLSR-10 cents of land in RS No.20, Kolari village to be acquired by Mattannur Municipality.  2) For GL tank, land near existing tank at Kotheri identified.  Request sent to GOK for 2nd land vide Lr No. 1459/DM I/(SU)/2017/KWA dated 02.02.2017 G.O issued from WRD

Sl. No.	Project Name	Project Code	Project Type	Project Location	Project Description	Project Cost (Cr)	Project Status
					<p>Package IV- Reservoir (15 Lakhs Litre at Iritty HSS Gravity Main (150 mm DI K9) 575m Clear Water Gravity main 450 &amp; 400 mm DI K9 pipe to GLSR at Iritty HSS, 11700 m</p>		<p>For 15 LL OHSR at Iritty Educational society- 25 cents of land in Keezhur village - RS No. 98/1 - to be acquired</p> <p>Request sent to GOK vide Lr No. 1459/DM I/(SU)/2017 dated 25.03.2017</p> <p>Land acquisition proposal submitted to District Collector, Kannur on 14/3/2017 To avoid KSTP road, different route is identified. Revised proposal to be approved.</p>
11		WRD003-02	Augment ation of WSS to Dharmad am panchaya th in Dharmad am Constitue ncy		<p>Package I -Gravity Main from Amukapally to Sump at Dharmadam – 250 mm DI K9 -1140m, 2.00 lakhs litre capacity Sump and Pump house at Dharmadam , Pumping Main from Sump at Dharmadam to OH Tank at Brennan college Campus – 250mm DI K9 – 600m 13 lakhs litre capacity OH Tank at Dharmadam , Brennan College campus and 2 Nos. 75 HP Centrifugal Pumpset - 3.03cr Distribution System – 90mm PVC pipe to 160mm PVC pipe and 200mm DI K9 pipe to 400mm DI K9 pipe – total length 80824m - 13.47 cr</p>	16.5	<p>Tender under scrutiny in H.O Lowest bidder is Sri. E.V. Raju 7.92% above</p>

Project Details					Financials		
Sl. No.	Project Name	Project Code	Project Description	Project Details	Estimated Cost (Lakh)	Actual Cost (Lakh)	Remarks
12	Water Resources	WRD003-03	Distribution Systems in 9 Projects	WSS to Kottayam Census Towns - Strengthening of Distribution system in Thalassery Taluk of Kannur District	Laying Distribution Network (450mm to 150mm DI K9 and 160mm to 90mm PVC -52885 m)	12	Kerala Water Authority
13		WRD003-04	Distribution Line Extension from ongoing WSS to Mananthavady, Edavaka and Nallooradu villages in Wayanad District	Package I 1. Supplying ,laying ,testing and commissioning of Distribution lines from Mananthavady OHSR ,Edavaka OHSR and Govt. College GLSR using 350 mm DI pipes to 90 mm PVC pipes and 150 mm DI K9 CWPM from the clear water sump at Choottakadavu to existing GLSR at Payyampally (WSS Vemam Nallooradu) including shifting of service connection to newly laid pipe lines.- 1267.50 lakh 2. Supplying ,testing, erection and commissioning of 2Nos 40 HP Centrifugal pump set (one as stand by) at Clear Water Pump House,Choottakadavu -15.0 lakh 3. Design and construction of retaining wall and yard filling at pump house and sub station -31 lakh 4. Design and construction of 4 m wide road to WTP at Choottakadavu-33 lakh.	18	Kerala Water Authority	
							Agreement executed.  Work awarded to lowest Tenderer Sri. E.V.Raju which is below 3.61%
							Work Order Issued Lowest bidder is Sri.C.T.Thambi, C/o T.D.Sunny Tharakan, Laloor Road, 12.21% below

Sl. No.	Project Name	Project ID	Project Type	Project Description	Estimated Cost (Cr)	Authority	Remarks
14	Water Resources	WRD003-05	Distribution Systems in 9 Projects	CWSS to Thiruvalli & Adjoining Villages- Phase I & II- Thiruvalli and Wandoor Part-1 1. Distribution System to Zone I-6.51 crore 2. Distribution System to Zone II and clear water pumping main for Wandoor. Part I-14.95 crore 3. Clear water pump set - Rs. 0.204 crore	22.2	Kerala Water Authority	Placed in KWA Board held on 07/06/2017 Lowest bidder is M/s TomCo Engineering (p) Ltd. 9.99 % below
15	Water Resources	WRD003-06	Distribution Systems in 9 Projects	Augmentation of Nenmara, Ayilur & Melarcode Water Scheme in Chittur & Alathur Taluks in Palakkad District (Phase II) Package I 1. OHSR at Nenmara (9.50 LL)- 1.93cr 2. Renovation of 7LL GLSR at Nenmara-0.2 cr 3. Renovation of existing GLSR at NSS college, Nenmara-0.4 cr 4. CWPM to Kaithachira OHSR in Ayilur Panchayath 4.38cr 4. Construction of 11.5LL OHSR at Kaithachira in Ayilur Panchayath 3.22cr 5. Supply and erection of Clear water pumpsets for Ayilur and Melarcode panchayaths 0.38cr	24.5	Kerala Water Authority	Work Order Issued Lowest bidder is Sri.David Mangan, Mangan House, Pallissery, Arattupuzha, Thrissur 7.42% below
				Package II 1. Supplying and Laying of distribution mains lines in Nenmara, Ayilur and Melarcode panchayath 3.5cr 2. Clear water pumping main TO Kadampidi OHSR n Melarcode Panchayath- 7.45 cr 3. Construction of 9.5LL OHSR at Kadampidi in Melarcode Panchayath -2.85cr			WORK TENDERED
16		WRD003-07		Water supply Distribution strengthening of Kadamakkudi Panchayath Package I strengthening of distribution system of Kadamakkudy Panchayath by supplying, laying PVC/HDPE/DI/MS/ GI pipes of various size and class by zoning the distribution network into 3 and the interconnecting with the newly constructed OHSRs at Kothad, Pizhala, Paliyamthuruth	12		Tender under processing in H.O Lowest bidder is Sri. K.O.Jose 3.96% below

17		WRD003-08	Water supply Distribution strengthening of Varappuzha Panchayath	Package I strengthening of distribution system of Varappuzha Panchayath by supplying, laying PVC/HDPE/DI/MS/GI pipes of various size and class and interconnecting with the OHSRs at Mannamthuruth and renovation of existing 15.5 MLD, WTP at Muppathadam to increase the production capacity to installed capacity of 15.5 mld	16.5		WORK TENDERED
18			W.S.S. to Perinadi	Package I 1.Distribution from sump near TP(Zone I)18.31cr 2. CWPM from TP to sump at Mannampuzha Low Level-1.39cr 3. Distribution from Edapramala Low Level (Zone 2)0.33cr 4.Distribution from Edapramala High Level (Zone 3)1.12cr 5.Distribution from sump at Mannampuzha Low Level Tank (Zone 4)0.75cr 6.Distribution from GLSR at Mannampuzha High Level Tank (Zone 5)0.72cr 7.Distribution from GLSR at Kottupara (Zone 6)1.67cr 8.Distribution from GLSR at Mampara (Zone 7)1.08cr 9.CWPM from sump at Mannampuzha Low Level to Mannampuzha High Level-0.15cr			Work Order Issued on 13/6/17 Lowest bidder is Sri.E.M Poulase 12.52% below

	Water Resources	WRD003-09	Distribution Systems in 9 Projects	& Athikkayam Villages in Pathanamthitta District (Phase - 2)	Package II 1) Laying Clear Water Pumping Main from Sump near Treatment Plant to Pancharamukku Sump cum Pump House 3.14cr 2) CWPM from TP to sump at Mundamala Low Level 0.32cr 3) CWPM from Sump at Mundamala Low level to GLSR at Mundamala High Level 0.49cr 4) Construction of 0.5 GLSR at Mundamala High Level 0.23cr 5) Construction of Pump House at Mundamala Low Level 0.23cr 6) Distribution from Mundamala Low Level tank (Zone 8) 0.39cr 7) Distribution from Mundamala High Level tank (Zone 9) 2.67cr 8) Distribution from sump at Pancharamukku (Zone 10) 2.22cr 9) Distribution from GLSR at Chembanmudi (Zone 11) 2.44cr 10) CWGM from GLSR at Kottupara to GLSR at Mampara 0.59cr 11) CWPM from Sump at Pancharamukku to Chembanmudi GLSR 0.84cr 12) Supply and Erection of Pump sets 0.62cr 13) Power Allocation and allied works 1.70cr	41.4	Kerala Water Authority	Location : Near existing GLSR at Perunad Panchayath 4 cents (Pump House at Mundamala) and 10 cents (Mundamala GLSR) required. Status: Land to be arranged by the Panchayath
19	Water	WRD010-01	New projects for	Improvements to Ramanattukara Water Supply Scheme by interlinking with WSS to Cheekode and adjoining	Package I 1. 250mm & 200mm Dia Clear water pumping main, distribution system, zone 1 & road restoration charges.	26	Kerala Water	Work was tendered but tenderers were not prequalified and so cancelled the tender and retendered on 11/5/2017 with due Date of Tender Submission on 06/06/2017
					Package II 1. Construction of 8.0LL OHSR, distribution system, zone II & road restoration charges 2. Electromechanical works (pumps & transformers). 3. Maintenance of Existing GLSR & Other contingencies			Work was tendered but tenderers were not prequalified and so cancelled the tender and retendered on 11/5/2017 with due Date of Tender Submission on 06/06/2017



20	Resources	WRD010-02	Irrigation and Drinking Water	Water Supply Scheme to Kalluvathukkal Parippally and Velinalloor villages - Phase I	Package I Design, construction of ,6m dia. Intake well , transformer room, approach road and retaining wall and other protection works at downstream side of Aduthala Bridge. Supplying, laying, Commissioning and maintaining of RWPM from Intake well to WTP at Kattupuram in Kalluvathukkal Panchayath Supply, Erection and Commissioning of Raw Water Pump sets and Electrical substation at Well cum pump house at Aduthala.	27	Authority	The proposed revenue purampokku for Intake well is 4.95 Ares(12 cents) in Kollam taluk & in kalluvathukkal village of block No: 39 and Resurvey No: 20. This land has to be handed over by Panchayath/Revenue authorities. Panchayath has already taken the necessary steps for handing over for getting permissive sanction from the revenue department
	Water Resources	WRD010-02	Distribution Systems in 9 Projects	Water Supply Scheme to Kalluvathukkal Parippally and Velinalloor villages - Phase I	Package II Construction of 10.00 MLD conventional type rapid sand filter Water Treatment Plant including 5.50 LL CW sump Construction of 11.5 Lakhs Litre OHSR at Kattupuram Supply, Erection of 2 Nos of 40HP Clear Water Pump sets From WTP To OHSR at TP SITE, Supplying and Laying 350mm DI K9 Clear Water Pumping Main from WTP sump to OHSR at TP site - 75m and construction of tranformer room electrification works of WTP & Pump house and erection of transformers.		Kerala Water Authority	The private land for the WTP is 1.2 acres , Resurvey No:306/3,306/10,306/14 of Kalluvathukkal Village . This private land has to be acquired by panchayath and handed over to KWA. Panchayath has already taken the necessary steps for acquiring the land on negotiated purchase basis.
					Package III Construction of new weir at Mannayam and strengthening of existing weir at aduthala and connected works			Estimate under preparation
					Package IV Rehabilitation of 1.5 MLD slow sand filter plant at Velinalloor			Estimate under preparation
					Package V-Strengthening of the existing weir constructed by the Irrigation department at Aduthala and its allied works			Estimate received from Irrigation dept.

21	Water Resources	WRD010-03	New projects for Irrigation and Drinking Water	WSS to Ambalapara Panchayath in Ottapalam Taluk, Palakkad District - Phase I	Package-1 1.Construction of CWPH at WTP premise at Ottappalam - 0.11cr 2.Construction of OHSR 8.5LL -1.72cr 3.Supplying and laying clear water pumping main from WTP to Murukkumpetta junction 350mm DI K9-7000m-5.3cr 4. Supplying and laying clear water pumping main from Murukkumpetta junction to existing booster station - 300mm DI K9 -300m-0.245cr 5.Supplying and laying clear water pumping main from Murukkumpetta junction to low level zone -150mm DI K9-1305m-0.43cr 6 Supplying and laying clear water pumping main Distribution line from low level OHSR to Murukkumpetta Junction 300mm DI K9-300mm DI K9 -1305m-0.8cr 7.Supplying and laying 250mm clear water pumping main to Higher level zone from existing Booster station -1500m-0.795cr Supplying and erection of Clear Water pumpsets and energisation	10	Kerala Water Authority	Work Order Issued Lowest bidder is Sri.Binu Mathew, Kottaviruthil House, Anaprampal, Thalavady 6.88% below
22		WRD010-04		Comprehensive WSS to Thachanattukara, Alanallur and Kottopadam panchayaths in Mannarkad taluk in Palakkad District.	Package I 1. Construction of intake well cum pump house, Leading pipe protection work and approach road-0.98cr 2. Construction of 19mld WTP and allied works-11.82cr 3. Supplying and laying Raw Water Pumping Main 500 DI K9 Pipe 6080m – 7.17cr 4.Supply and erection of Raw water pumpsets extension of power line and energisation-1.32cr	22		Placed in KWA Board held on 07/06/2017 Lowest bidder is Sri.Binu Mathew, Kottaviruthil House, Anaprampal, Thalavady 11.18% below

Project Details					Financials			
Sl. No.	Project Name	Project Code	Project Description	Project Location	Estimated Cost (Rs. Crores)	Authority	Remarks	
23	Water Resources	WRD010-05	New projects for Irrigation and Drinking Water	Water Supply Scheme to Tanur Municipality and adjoining Panchayats - phase 1	Package I 1. Well cum pumphouse and protection work- 12m dia 2. 800 mm dia DI K9 Raw Water Pumping Main-14.30 Km & Contingencies	100	Kerala Water Authority	Work TENDERED 4 Offers received and all are prequalified. Price bid opened
				Package II 1. 45 MLD Water Treatment Plant 2. 96 LL OH Reservoir 3. 800Mm dia DI- K9 Clearwater pumping main	Work TENDERED Due Date of Tender Submission extended to 28/06/2017			
				Package III 1. Raw water pump set -500 HP 2. Clear water pump set- 180 HP & Contingencies 3. Power line extension & Transformer -(1600 KVA & 500 KVA) & Contingencies 4. Substation building-	This package will be tendered later on progress of works of other packages			

